

Known issue with TASCAM USB Audio Devices and System Audio in Windows 8.1 Update

28.04.2014

A problem may occur after installing Windows 8.1 Update 1 (KB2919335), and connecting a TASCAM USB Audio Interface and setting the Windows Sound settings for the Default audio Format for shared mode to 24 bit. This may cause a STOP Error (Blue screen) when a system audio event is played back.


Tascam is preparing a new Windows driver to resolve this issue and will publish it on this website (http://tascam.eu/) when it is ready.

Until the new driver is available, please use only the 16-bit settings in the Windows Sound Speaker properties.


NOTE

- This setting does not affect audio through your DAW software to the TASCAM USB Audio Interface when using ASIO.
- This setting does not affect audio through your DAW software to the TASCAM USB Audio Interface when using ASIO.

1 Open Control panel -> Sound.



- 2 Right click on Speakers/TASCAM US-XXXX and select Properties.
- B Click on the Advanced tab.



4 Select any of the available 16-bit settings.